No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
11	Providing and fixing teakwood doors 4′ ×7′ with frames 4½″×3½″ in section with pannelled shutters 1½″ thick having top 1½ fixed with expanded metal with iron clamps and fitting including two coats of silicate painting .. .	S.ft.	56	1 8 0		
12	Providing and fixing teakwood windows 3′ ×5′ with frames 3½″×4″ in section ¾″ dia. iron bars and pannelled shutters 1¼″ thick iron clamps iron fittings, etc., including two coats of silicate painting	,,	60	1 10 0		
13	Providing teakwood windows with ¾″ iron bars without shutters having expanded metal fixed as per existing design including two coats of silicate painting.	,,	58	1 4 0		
14	Stucco plastering with lime mortar with mortar bands alround as per design including cement wash	Sqr.	3·60	4 8 0		
15	Flooring with burnt stone slabs 3″ to 4″ thick one line dressed over 3″ burnt stone jelly concrete and pointed with cement	,,	6·60	30 0 0		
16	Plastering with lime mortar	,,	29·12	2 12 0		
17	Removing and refixing Cuddapah slabs on new 3″ thick burnt stone jelly concrete.	,,	1·44	8 0 0		
18	Cement pointing	,,	4·00	3 0 0		
19	Removing and refixing the steps in mortar with necessary masonry	S.ft.	96	0 1 0		
20	Mortar band over roof	R.ft.	48	0 2 0		
21	Providing burnt stone slabs 6″ thick and fixing in mortar	S.ft.	74	0 4 6		

N. LAKSHMINARASIMIAH,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 20th September 1939.

The attention of the public is invited to the detailed notification, dated 19th September 1939, published on pages 1954-1956, Part VI of the *Mysore Gazette*, dated 28th September 1939, regarding tenders for the maintenance work to Nambihalli Doddakere, Register No. 93-426 of Srinivaspur Taluk.

The last date for receiving tenders is 16th October 1939 up to 2 P.M.

Abstract Notification dated 20th September 1939.

The attention of the public is invited to the detailed notification, dated 19th September 1939, published on pages 1956-1959, Part VI of the *Mysore Gazette*, dated 28th September 1939, regarding tenders for the construction of Quarters for the Inspector of Mines and Explosives at Kolar Gold Fields.

The last date for receiving tenders is 16th October 1939 up to 2 P.M.

Notification dated 29th September 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 23rd October 1939, for restoring Cholaghatta Mavinkere Reg. No. 813—530 in Kolar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Restoring Cholaghatta Mavinkere Reg. No. 813—530 in Kolar Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by Treasury challan for earnest money of Rs. 450 paid to the *treasury* to the credit of 17 (*a*) P. W. Deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 23rd October 1939 at 2 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs.....

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for each item on the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of dispute of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P.W.D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on payment of four annas per form.

Abstract estimate for restoring Cholaghatta Mavinkere Reg. No. 812/530, Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. *Bund at* 56·50 *top width* 6′ *slope* 1½ *to* 1 & 2 : 1.		Rs. a. p.		Rs.
1	Jungle clearing with removal of roots, etc. ..	Grade	1 0 0	22	
2	Removing ant-hills and refilling them with sand etc., complete	,,	1 0 0	22	
3	Removing top soil and cutting grips to trenches for the seat of new earth	,,	2 0 0	22	
4	Cutting trenches in the centre of bund and refilling the same with clay and gravel with consolidation to prevent percolation	C.yd.	0 6 0	825	
5	Earthwork to bund with watering and consolidation	,,	0 3 0	9,316	
6	Turfing	S.yd.	0 0 9	6,211	
7	Gravel-backing 9″ thickness	C.yd.	0 6 0	806	
8	Providing and fixing new grade stones including cutting figures and painting, etc., complete ..	Each	1 12 0	22	
9	Do Index Stones do ..	,,	0 6 0	22	
10	Do Reg. No. and Date stone do ..	,,	3 0 0	1	
11	Do B. M. Stones do ..	,,	2 8 0	2	
12	Do Gauge stone do ..	,,	15 0 0	1	
13	Removing and resetting old stone including 25 per cent jelly carted and stacked as per statement.	C.yd.	0 12 0	614	
14	New stone revetment work as per statement ..	,,	1 12 0	1,328	
	II. *Constructing a Cast Iron Pipe Sluice No. 1 for* 8″ *dia., at R. L.* 45·00.				
1	Cut opening the bund and filling in with select earth with watering and consolidation	C.yd.	0 6 0	108	
2	Earthwork excavation for foundation	,,	0 3 0	12	
3	Stone jelly concrete in surki mortar	C.ft.	0 4 3	238	
4	Burnt stone in surki mortar	,,	0 5 0	312	
5	Burnt stone slabs 4″ to 6″ thick dressed and fixed ..	S.ft.	0 5 0	98	
6	Pointing with cement mortar	Sqr.	4 8 0	4·03	
7	Supplying and fixing 8″ Cast Iron pipes including Railway freight, cart-hire, etc., complete ..	R.ft.	4 0 0	27	
8	Drilling holes to the slabs	L. S.	..	..	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	III. *Constructing Sluice No. 2.*				
	As per details above				
	IV. *Constructing a masonry weir 100 ft. long at 52·00, Left Flank.*				
1	Earthwork excavation for foundation (for forming bank)	C.yd.	0 3 0	194	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 3	438	
3	Burnt stone in surki mortar	„	0 5 0	1,191	
4	Burnt stone slabs 6" thick dressed and fixed	S.ft.	0 5 0	188	
5	Pointing with cement mortar	Sqr.	4 8 0	13·12	
6	Rough stone apron with 40 per cent of jelly carted and stacked	C.yd.	1 8 0	163	
7	Joggle joints ½ of a foot to go in each slab	Each	0 12 0	13	
8	Jelly packing to apron	C.yd.	1 0 0	18	
9	Ramping with clay to the front side	C.yd.	0 4 0	22	
	V. *Constructing waste weir at 52·00 Right flank, 100 ft. long.*				
1	Earthwork excavation for foundation (for forming bank)	C.yd.	0 3 0	187	
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 3	454	
3	Burnt stone in surki mortar	„	0 5 0	1,221	
4	Burnt stone slabs of 6" thick dressed and fixed	„	0 5 0	187	
5	Pointing with cement mortar	Sqr.	4 8 0	13·91	
6	Rough stone apron	C.yd.	1 8 0	220	
7	Dry stone packing below apron	„	1 0 0	27	
8	Ramp filling in with clay	„	0 4 0	39	
9	Joggle joints 8' C to C	Each	0 12 0	13	

C. R. IYENGAR,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 18th August 1939.

The attention of the public is invited to the notification dated 17th August 1939, on pages 1659-1661, Part VI of the *Mysore Gazette*, dated 24th August 1939, calling for tenders for the work of "Repairing the big car of Sri Kalaseswaraswamy Temple at Kalasa, Mudgere Taluk."

The last date of receipt of tender in this office is hereby extended till the end of 9th October 1939.

M. A. RAMANUJAM,
Executive Engineer.

MEDICAL DEPARTMENT

OFFICE OF THE SECRETARY, VICTORIA, MINTO AND VANI VILAS HOSPITALS, BANGALORE.

Tender Notification dated 30th September 1939.

Notice is hereby given that sealed tenders, in triplicate, on half-sheet foolscap sized paper, will be received at the Office of the Secretary, Victoria, Minto Ophthalmic, Vani Vilas and Children's Hospitals, Bangalore, in his office at the Victoria Hospital by the undersigned at 11 A.M. on Monday the 6th November 1939, for the supply of articles of diet, etc., required for the use of the said Hospitals, from 1st January 1940 to 31st December 1940, inclusive.

2. No tender will be received after the date and hour abovementioned.

3. Tenders to be superscribed "Tender for the supply of *provisions* to the Victoria, Minto Ophthalmic, Vani Vilas and Children's Hospitals."

4. No tender will be received unless accompanied by a deposit of Rs. 300 in cash, or currency notes, or treasury receipts.